



VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

Ref. No.Revised VP/PM/F. 13/Res-Villas/Com-wall/Swim-Pools//2022-23/517
dt.:- 12-5-2022

CONSTRUCTION LICENCE

Licence is hereby granted to **Models Construction Pvt Ltd r/o St. Inez, Panaji-Goa**, in pursuance of Resolution No. 2(1) duly approved by the Village Panchayat Pilerne – Marra in its meeting held on dt. 29-4-2022 for carrying out the proposed amalgamation of plots and construction of Residential Villas (3 nos) Swimming pool and Compound wall in Sy. No.40/10,11 and 12 at Marra, Village Pilerne, Bardez Taluka.

Subject to the following conditions:-

1. The applicant shall notify the Panchayat for giving the alignment of the building.
2. The Applicant has to comply the following Directives of the High Court on Solid Waste Management.
 - a. Applicant Shall dispose the Construction debris at his own level and the same shall be taken to the designated site as per the disposal plan given by the applicant in the affidavit at his own expenses .
 - b. Applicant Shall produce the certificate issued by the concerned PWD officials of designated sites as mentioned in the said notification dated 07/03/2018.
 - c. Failing to comply clause (a) and (b) the penalty shall be imposed to the applicant at the rate of 0.5% on the total cost of the project and also the construction licence issued to the applicant shall be withdrawn/cancelled .
3. Construction & Demolition waste Management Rule 2016 and Solid Waste Management Rule 2016 and Solid waste Management Rules Shall be Strictly followed.
4. The construction should maintain the minimum prescribed horizontal and vertical clearances from any overhead electrical line passing adjacent to the construction.
5. All RCC/Structural works shall be designed and supervised by the Engineer who has signed the Structural Liability Certificate submitted to the Panchayat.
6. No material for construction or earth from excavation or any other construction material shall be stacked on the Public roads.
7. The Building should not be occupied unless the occupancy certificate is obtained from the Panchayat.

The applicant should construct a separate soak pit in order to derivate in the sullage water.

Any soak pit should be constructed at a minimum distance of 15 meters away from any well.





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

Ref. No. Revised VP/PM/F. 13/Res-Villas/Com-wall/Swim-Pools//2022-23/517 dt.:- 12-5-2022

... Pg. 2...

10. The construction license shall be revoked if the construction work is not executed as per the approved plans and the statements therein and whenever there is any false statement or misrepresentation of any material passed approved or shown in the application on which the permit was based
11. The ventilation pipe of the septic tank should be provided with a mosquito net.
12. The Applicant should connect the pipelines from their Latrines / WC's to the sewerage line at their own cost, when the sewerage line is commissioned.
13. The applicant should fix a board at a prominent place whenever the construction is started, indicating the number, the date and the authority for which the licence for development work has been granted .
14. All the building material and other rubbish should be Cleared from the construction site before applying for the Occupancy certificate
15. Water storage tanks shall be provided with mosquito proof lids and over flow pipes. The tanks should be provided with access ladders wherever necessary.
16. The drains surrounding the plot if any should be constructed with PCC and should be covered with removable RCC slabs of sufficient thickness.
17. The applicant should gift the road widening area to the Village Panchayat before applying for the Occupancy certificate, if the applicant has utilized the extra FAR in lieu of the road widening affecting the plot.
18. The applicant should plaster and paint the building Internally as well as externally before applying for Occupancy certificate. Exposed rick / laterite / concrete / Stone / ashlar masonry finish to buildings will also be permitted.
19. The applicant should provide a dustbin at a convenient Place accessible for the Panchayat vehicle for collection of garbage.
20. Garages and Parking areas shown in the approved plan shall be strictly used for Parking purposes only and should be easily accessible to vehicles. No commercial activities shall be allowed in these areas.
21. Road widening area shall be asphalted to the existing road level before applying for occupancy certificate.
22. Access up to the entrance of the building is to be paved and provided with drainage facilities.



.... Cont. Pg. 3



VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vpilernemarra81@gmail.com

Ref. No.Revised VP/PM/F. 13/Res-Villas/Com-wall/Swim-Pools//2022-
23/517 dt.:- 12-5-2022

... Pg. 3

23. Space for parking of vehicles is clearly demarcated on the ground.
24. No Restaurants / Bars will be permitted in the shops unless a separate soak pit is provided besides confirming to the rules in force.
25. No commercial activities will be permitted in the shops unless a separate permission is obtained from this Panchayat.
26. All Temporary sheds / Existing buildings shown to be demolished in the plan are demolished before applying for Occupancy certificate.
27. Fire Escape staircases, if applicable shall be constructed as indicated in the approved plans.
28. All internal courtyards should be provided with drainage outlet.
28. The applicant should maintain all existing natural drains in the plot and should not block them at any stage.
29. No soak pit or other structures should come in the road widening area.
30. The plot boundary should be cordoned off by continuous Sheet fencing either of wood or metal during the construction period.
31. The construction of compound wall should not obstruct any pathway or any public access. The applicant shall make necessary arrangements for smooth flow of rain water by keeping adequate openings in the compound wall for the purpose.
32. Storage of water should be done in such a way that mosquito breeding doesn't take Place either by introducing fish in the tanks / wells or properly covering the iron drums / plastic tanks etc. or by observing dry day once a week.
33. Overhead tanks / sumps are provided with mosquito proof lids and other pipe fittings without any hole for the entry of mosquitoes. Outlet is to be covered by muslin / wire mesh. Ladder for inspection of the tank to be installed if required.
34. Curing water collections should be treated with anti-Larval Chemicals by the builders/contractors .
35. Not to engage Labourers for any construction/ building work unless they are Screened for malaria and posses health cards. These cards are to be renewed regularly every 3 month. Also arrangement should be done to get their blood tested immediately in case of fever and ensure that full treatment is taken in consultation with NVBDCP programme.
36. Labourers to be provided with basic amenities like proper shelter, water for drinking and domestic proposes, proper sanitary conditions including toilet facilities.
37. No gates shall open outwards on to the road.



.... Cont. Pg. 4.



VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

Ref. No. Revised VP/PM/F. 13/Res-Villas/Com-wall/Swim-Pools//2022-
23/517 dt.:- 12-5-2022

-4-

38. To fill the pits, ditches water pools etc to avoid stagnation and to ensure no mosquito breeding sites in and around specially in unused item like tyres, bottles, tins etc.
39. Drains/Nallahs to be maintained clean around the site so that there is no blockade to flow of water. The gradient should be proper for drainage/flow and also proper cleaning of water should be done.
40. The Health units at the respective levels should be involved in the planning process.
41. The construction of the compound wall, if any should be as per the approved plan. The applicant shall inform this Panchayat after the completion of the compound wall.
42. Drinking water well should be 15 meters away from any soak pit.
43. All the conditions stipulated in the Technical clearance order Town and Country Dept Mapusa bearing No. TPB/6422/Marra/TCP-2022/1825 dated 8-4-2022
44. All the conditions stipulated in the NOC bearing No. PWD/ SD-IV/ PHE-N/F.13/38/22-23 dated 20-4-2022 from Assistant Engineer, PWD, Porvorim, Bardez-Goa.
45. All the conditions stipulated in the NOC bearing No.1/10/TECH/O&M/SD.II/POR/2022-23/118 dt. 25-4-2022 from Assistant Engineer, Electricity Dept Porvorim, Bardez-Goa.
46. The Waste generated during the Course Construction/repair/renovation etc. shall be disposed off by the applicant/s in a scientific manner without harming the environment in its own property.
47. The Applicant has to construct the composting pits for the disposal of wet garbage generated from the premises.
48. The information furnished by the applicant for obtaining the permission for Revised Construction of Residential Villas (3 nos) Swimming pool and Compound wall in Sy. No.40/10,11 and 12 at Marra, Bardez-Goa. if found to be false at later stage, or if the conditions Stated herein above are not complied with, the Permission issued shall be liable to be withdrawn without pre-judice to the legal action that may be taken against the application.

Cont...5





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

Ref. No.Revised VP/PM/F. 13/Res-Villas/Com-wall/Swim-Pools//2022-23/517 dt.:- 12-5-2022

... Pg. 5...

THIS LICENCE IS VALID FOR A PERIOD OF THREE YEARS FROM THE DATE OF ISSUE OF THIS LICENCE. 12-5-2022 to 11-5-2025. RENEWAL IF REQUIRED SHALL BE APPLIED WITHIN THE PERIOD OF THE VALIDITY OF THE LICENCE. HE/SHE HAS PAID THE LICENCE FEES TO THE TUNE OF(RUPEES NIENTY TWO THOUSAND TWO HUNDRED TWENTY NINE ONLY)) AND SANITATION FEES(RUPEES FOURTY SIX THOUSAND ONE HUNDRED FIFTEEN ONLY)

Const. fees..... Rs.92,229/-


Sanitation feesRs. 46,115/- Paid vide receipt No.

dt. 12-5-2022

Labour cess @ of 1% as per Construction Estimate/Valuation Cost is Rs. 1,84,35,800/- Paid labour cess of Rs. 1,84,358/- vide receipt no. dt. 12/5/2022

This carries the embossed seal of Panchayat Office Village Panchayat Pilerne - Marra.





PETER MARTINS
V.P. SECRETARY,
V.P. PILERNE-MARRA, BARDEZ-GOA.

To,
Models Construction Pvt Ltd r/o St. Inez, Panaji-Goa

Copy to:-

1. Town and Country Planning Department, Mapusa, Bardez - Goa .

Seen


SANDEEP K. BANDODKAR
SARPANCH
V.P. PILERNE - MARRA