



VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : yppilernemarra81@gmail.com

Ref. No.VP/PM/F.7 /Res. Villas 1 to 9 (9 nos) /Swim-Pool/Com-wall/2025-26/220 Dt.- 30-4-2025

CONSTRUCTION LICENCE

Licence is hereby granted to **Mr. Harpreet Sachdeva and Mrs. Sarika Sachdeva** r/o A-1/132 , Safdarjung Enclave South West Delhi , in pursuance of **Judgement and Order dated 25-4-2025 issued by the Additional Director of Panchayats-I Panaji-Goa in Appeal No. ADP-I/Pilerne-Marra/P.A.110/2025** for carrying out proposed Construction of **Residential Villas 1 to 9 (9 nos), Swimming Pools and Compound wall** in Sy. No. 86/16 of Village Marra , Bardez Taluka.

Subject to the following conditions:-

1. The applicant shall notify the Panchayat for giving the alignment of the building.
2. The Applicant has to comply the following Directives of the High Court on Solid Waste Management.
 - a. Applicant Shall dispose the Construction debris at his own level and the same shall be taken to the designated site as per the disposal plan given by the applicant in the affidavit at his own expenses .
 - b. Applicant Shall produce the certificate issued by the concerned PWD officials of designated sites as mentioned in the said notification dated 07/03/2018.
 - c. Failing to comply clause (a) and (b) the penalty shall be imposed to the applicant at the rate of 0.5% on the total cost of the project and also the construction licence issued to the applicant shall be withdrawn/cancelled .
3. Construction & Demolition waste Management Rule 2016 and Solid Waste Management Rule 2016 and Solid waste Management Rules Shall be Strictly followed.
4. The construction should maintain the minimum prescribed horizontal and vertical clearances from any overhead electrical line passing adjacent to the construction.
5. All RCC/Structural works shall be designed and supervised by the Engineer who has signed the Structural Liability Certificate submitted to the Panchayat.
6. No material for construction or earth from excavation or any other construction material shall be stacked on the Public roads.
7. The Building should not be occupied unless the occupancy certificate is obtained from the Panchayat.

Cont..2





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : yppilernemarra81@gmail.com

Ref. No.VP/PM/F.7 /Res. Villas 1 to 9 (9 nos) /Swim-Pool/Com-wall/2025-26/220 Dt.- 30-4-2025

... Pg. 2...

8. The applicant should construct a separate soak pit in order to derivate in the sullage water.
9. Any soak pit should be constructed at a minimum distance of 15 meters away from any well.
10. The construction license shall be revoked if the construction work is not executed as per the approved plans and the statements therein and whenever there is any false statement or misrepresentation of any material passed approved or shown in the application on which the permit was based
11. The ventilation pipe of the septic tank should be provided with a mosquito net.
12. The Applicant should connect the pipelines from their Latrines / WC's to the sewerage line at their own cost, when the sewerage line is commissioned.
13. The applicant should fix a board at a prominent place whenever the construction is started, indicating the number, the date and the authority for which the licence for development work has been granted
14. All the building material and other rubbish should be Cleared from the construction site before applying for the Occupancy certificate
15. Water storage tanks shall be provided with mosquito proof lids and over flow pipes. The tanks should be provided with access ladders wherever necessary.
16. The drains surrounding the plot if any should be constructed with PCC and should be covered with removable RCC slabs of sufficient thickness.
17. The applicant should gift the road widening area to the Village Panchayat before applying for the Occupancy certificate, if the applicant has utilized the extra FAR in lieu of the road widening affecting the plot.
18. The applicant should plaster and paint the building Internally as well as externally before applying for Occupancy certificate. Exposed rick / laterite / concrete / Stone / ashlar masonry finish to buildings will also be permitted.
19. The applicant should provide a dustbin at a convenient Place accessible for the Panchayat vehicle for collection of garbage. Garages and Parking areas shown in the approved plan shall be strictly used for Parking purposes only and should be easily accessible to vehicles. No commercial activities shall be allowed in these areas.

Cont...





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

Ref. No.VP/PM/F.7 /Res. Villas 1 to 9 (9 nos) /Swim-Pool/Com-wall/2025-26/220 Dt.:- 30-4-2025

... Pg. 3

22. Access up to the entrance of the building is to be paved and is provided with drainage facilities.
23. Space for parking of vehicles is clearly demarcated on the ground.
24. No Restaurants / Bars will be permitted in the shops unless a separate soak pit is provided besides confirming to the rules in force.
25. No commercial activities will be permitted in the shops unless a separate permission is obtained from this Panchayat.
26. All Temporary sheds / Existing buildings shown to be demolished in the plan are demolished before applying for Occupancy certificate.
27. Fire Escape staircases, if applicable shall be constructed as indicated in the approved plans.
28. All internal courtyards should be provided with drainage outlet.
29. The applicant should maintain all existing natural drains in the plot and should not block them at any stage.
30. No soak pit or other structures should come in the road widening area.
31. The plot boundary should be cordoned off by continuous Sheet fencing either of wood or metal during the construction period.
32. The construction of compound wall should not obstruct any pathway or any public access. The applicant shall make necessary arrangements for smooth flow of rain water by keeping adequate openings in the compound wall for the purpose.
33. Storage of water should be done in such a way that mosquito breeding doesn't take Place either by introducing fish in the tanks / wells or properly covering the iron drums / plastic tanks etc. or by observing dry day once a week.
34. Overhead tanks / sumps are provided with mosquito proof lids and other pipe fittings without any hole for the entry of mosquitoes. Outlet is to be covered by muslin / wire mesh. Ladder for inspection of the tank to be installed if required.
35. Curing water collections should be treated with anti-Larval Chemicals by the builders/contractors.
36. Not to engage Labourers for any construction/ building work unless they are Screened for malaria and posses health cards. These cards are to be renewed regularly every 3 month. Also arrangement should be done to get their blood tested immediately in case of fever and ensure that full treatment is taken in consultation with NVBDCP programme.
37. Labourers to be provided with basic amenities like proper shelter water for drinking and domestic proposes, proper sanitary conditions including toilet facilities.

.... Cont.





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com


Ref. No.VP/PM/F.7 /Res. Villa 1 to 9 (9 nos) /Swim-Pool/Com-wall/2025-26/220 Dt.- 30-4-2025

... Pg. 4...

38. No gates shall open outwards on to the road.
39. To fill the pits, ditches water pools etc to avoid stagnation and to ensure no mosquito breeding sites in and around specially in unused item like tyres, bottles, tins etc
40. Drains/Nallahs to be maintained clean around the site so that there is no blockade to flow of water. The gradient should be proper for drainage/flow and also proper cleaning of water should be done
41. The Health units at the respective levels should be involved in the planning process.
42. The construction of the compound wall, if any should be as per the approved plan. The applicant shall inform this Panchayat after the completion of the compound wall.
43. Drinking water well should be 15 meters away from any soak pit.
44. All the conditions stipulated in the Technical clearance order Bearing No. TPB/10025/MARRA/TCP-2024/8030 dated 30-9-2024 should be strictly followed.
45. All the conditions stipulated in the NOC bearing No. DHS/2024/DHS0901/00900/119 dated: 24-10-2024 from Primary Health Centre Candolim, Bardez-Goa , should be strictly followed.
46. All the conditions stipulated in the NOC bearing No. PWD/ SD-IV/ WD.XVII/W.S./F.13/2024-25/529 dt. 15-11-2024 from Assistant Engineer, PWD, Porvorim, Bardez-Goa.
47. All the conditions stipulated in the NOC bearing No.1/10/TECH/O and M/SD.II/POR/2024-25/1618 dt. 1-11-2024 from Assistant Engineer, , Electricity Dept. Bardez-Goa.
48. The Waste generated during the Course Construction/repair /renovation etc. shall be disposed off by the applicant/s in a scientific manner without harming the environment in its own property.
49. The Applicant has to construct the composting pits for the disposal of wet garbage generated from the premises.

The information furnished by the applicant for obtaining the permission for Construction of Residential Villas 1 to 9 (9nos), Swimming Pools and Compound wall in Sy. No. 86/16 of Village Marra , Bardez-Goa. if found to be false at later stage, or if the conditions Stated herein above are not complied with, the Permission issued shall be liable to be withdrawn without prejudice to the legal action that may be taken against the application

Cont.





VILLAGE PANCHAYAT PILERNE MARRA

Bardez - Goa

PH : 2407466

Email : vppilernemarra81@gmail.com

50. Ref. No.VP/PM/F.7 /Res. Villas 1 to 9 (9 nos) /Swim-Pool/Com-wall/2025-26/220 Dt.- 30-4-2025

-5-

THIS LICENCE IS VALID FOR A PERIOD OF THREE YEARS FROM THE DATE OF ISSUE OF THIS LICENCE. 30-4-2025 to 29-4-2028 RENEWAL IF REQUIRED SHALL BE APPLIED WITHIN THE PERIOD OF THE VALIDITY OF THE LICENCE. HE/SHE HAS PAID THE LICENCE FEES TO THE TUNE OF(RUPEES FOUR LAKHS THIRTY ONE THOUSAND FOUR HUNDRED THIRTY TWO ONLY AND SANITATION FEES RUPEES TWO LAKHS FIFTEEN THOUSAND EIGHT HUNDRED SIXTEEN ONLY)

Const. fees Rs. 431432=00

Sanitation fees Rs. 215816=00

Paid vide receipt No 984/68 dt. 30-4-2025

Note:- Labour cess @ of 1% as per Construction Estimate/Valuation Cost Rs.8,62,76,404/- Paid labour cess of Rs. 862764/- vide receipt No.984/69Dated:- 30-4-2025

This carries the embossed seal of Panchayat Office Village Panchayat Pilerne - Marra.


KESHAV N. PHADTE
V.P. SECRETARY,
V.P. PILERNE-MARRA, BARDEZ-GOA.



To,
Mr. Harpreet Sachdeva and Mrs. Sarika Sachdeva r/o A-1/132 ,
Safdarjung Enclave South West Delhi

Copy to:-

1. Sarpanch of V.P. Pilerne-Marra Mrs. Reshma S. Bandodkar for information.
2. Town and Country Planning Department, Mapusa, Bardez - Goa .