


Government of Goa Directorate of Fire & Emergency Services

St. Inez, Panaji, Goa - 403 001 - India



File No.: DFES/FP/HB/151/22-23/ 3/9

Date: 14.11.2022.

NO OBJECTION CERTIFICATE

(Rule 26)

In pursuance of the Goa State Fire Force Act, 1986 and Rules 1997 read with Clause No.15.2 of The Goa Land Development and Building Construction Regulations, 2010 and Government Notification No.3/5/97-HD(G)Part/3934 dated; 17.12.2014. No Objection is hereby granted to M/s. Tridentia Developers for their Residential Building "Tridentia Panache - Block C" situated at Property bearing Chalta No. 34 of P.T Sheet No. 129, Gogol, Margao, Goa for having complied with the Fire Protection Arrangements (Annexure), which can be safely and effectively used at all material times, subject to the conditions as prescribed in the enclosed schedule. The next date of inspection is on 14.11.2023.

> (NITIN RAIKER) DIRECTOR FIRE & EMERGENCY SERVICES

Encl:-Annexure & Schedule.

To.

Shri Paresh Sawardekar, Managing Partner, M/s. Tridentia Developers, Prudential Panache, 1st Floor, Near Chinmaya Mission, Gogol, Margao, Goa.

rs/-

Phone Nos.: +91 (832) 2225500 / 2425101 Directorate of Fire & Emergency Services

Fax No.: +91 (832) 2226100 www.dfes.goa.gov,in Email:dir-fire.goa@nic.in

ANNEXURE

1. Name of the Building : "Tridentia Panache – Block C" situated at

Property bearing Chalta No. 34 of P.T Sheet

No. 129, Gogol, Margao, Goa.

2. Height of the Building : 27.00 Mtrs.

3. Number of Floors : Basement, Stilt plus Eight floors.

4. Floor Wise Built up Area : Basement floor - 2895.28 Sq.mtrs.

804.24 Sq.mtrs Stilt floor 849.52 Sq.mtrs. First floor 849.52 Sq.mtrs. Second floor Sq.mtrs. 849.52 Third floor Sq.mtrs. 849.52 Fourth floor 849.52 Sq.mtrs. Fifth floor Sq.mtrs. 849.52 Sixth floor Sq.mtrs. 849.52 Seventh floor 849.52 Sq.mtrs. Eight floor

5. Area of the Plot : 15536 Sq.mtrs.

6. Total Built up Area : 10495.68 Sq.mtrs.

7. Name of the Owner of the : Shri Paresh Sawardekar,

Premises Managing Partner,

M/s. Tridentia Developers, Prudential Panache, 1st Floor,

Near Chinmaya Mission, Gogol, Margao, Goa.

8. Person to be notified in case : Mr Parag Sabnis,

of Emergency and Tel. No. Tel.No. 9822135130

FIRE PROTECTION ARRANGEMENTS:-

a) Fire Hydrants (External) : 01 No. of 63 mm. Standard instantaneous

coupling, 01 No. of Hose Boxes, 02 Nos. of RRL Hose of 15 mtrs. length and 01 No. Emergency Branch pipe provided in the

premises.

b) Landing Valves : 08 Nos. of Standard instantaneous 63 mm

Outlet, 08 Nos. of Hose Boxes with 16 Nos. of R.R.L. Hoses of 15 mtrs. length and 08 Nos. Emergency Branch pipe provided and

distributed on all the floors of the building.

c) Fire Brigade Inlet : 01 No. of Two way Fire Brigade Inlet of

63 mm instantaneous coupling provided in the

building.

d) Hose Reel Hose System Conforming to IS:884/1984. 08 Nos. of Hose Reel Hose of 30 mtrs. length each provided and distributed on all the floors of the building.

e) First Aid Fire Fighting Equipments

08 Nos. of Dry Chemical Powder Extinguishers (ABC Type) of 4 Kg capacity, 02 Nos. of Dry Chemical Powder Extinguishers of 4.5 Kg conforming to BIS: 15683/2006 provided and distributed on all floors of the building.

f) Manually Operated Fire Alarm System : 01 No. Fire Alarm Panel on the Ground floor and 08 Nos. Manual Call Points with Hooters provided in the building.

g) Exits

One centrally located staircase of 1.40 mtrs. width and One Fire Escape staircase of 1.40 mtrs provided in the building.

h) Exit Signs

Directional Exit Signs provided.

i) Water Capacity

Underground Tank of 50,000 liters provided at Ground Level.

Overhead Tank of 25,000 litres provided at the terrace level.

i) Pump Capacity

: Jockey Pump - 180 LPM Terrace Pump - 900 LPM Main Pump - 2280 LPM

k) Alternate Power Supply Arrangements Diesel Generator Set of 165 KVA provided.

Periodical inspection of Fire Protection System

Yearly. The next date of inspection is on 14.11.2023.

(NITIN V. RAIKER)
DIRECTOR
FIRE & EMERGENCY SERVICES

SCHEDULE

The owner/management shall comply with the requirements as indicated in the schedule. Contravention of any of these requirements as indicated below shall lead to the cancellation of the certificate without any prejudice.

- 1. All the Means of Escape shall be properly maintained and kept free from obstruction of all type of combustible storage.
- 2. All Entry/ Exit doors through which a person may have to pass shall not be locked or fastened.
- 3. On those occasions, if disabled and handicapped persons are present in the premises, such special arrangements as may be necessary in the circumstances shall be made so as to enable all persons to leave the premises safely in the event of fire.
- 4. The Diesel Generator provided for the Fire systems viz. Corridor lighting, Fire Alarm System, Fire Pumps, Lift etc. shall be checked and maintained in functional condition for use in the event of any emergency.
- 5. All fire fighting equipments installed in the premises shall be maintained in efficient working order.
- 6. All portable Fire Extinguishers shall be examined at least once annually and tested by a competent person.
- 7. Fire Pumps, Fire Hydrants, Landing Valves and Hose Reel Hose shall be tested monthly to ensure that they are in working order and produce satisfactory jet of water to reach to the farthest point.

- 8. The Manual Call Points and Hooters connected to the Fire Alarm System shall be tested weekly using a different Manual Call Point for each successive test to ensure that it operates satisfactorily. The results of such inspection shall be recorded in the log book.
- 9. A logbook shall be maintained, in which details of periodical Tests/ Examination of the Fire Detection & Protection Systems, Fire Drills conducted shall be mandatorily recorded. The same should be readily available for inspections as and when required by the inspecting authority.

10. Fire Drill shall be conducted in the premises at least once every three months.

(NITIN V. RAIKER)
DIRECTOR
FIRE & EMERGENCY SERVICES