R/ W LINE
20.40
22.00
14.00
13.50
AREA UNDER ROAD WIDENING = 3557.00
30.40
32.30
31.50
27.90
36.60
29.50
30.00
30.00
30.25
32.30
33.10
29.00
46.90
42.90
27.10
RAILWAY LINE
OPEN SPACE 7100.00
OPEN SPACE
OPEN SPACE
ROAD WIDENING AREA = 2180.00
A=5700.00
B=7395.00
D=7800.00
ROAD WIDENING AREA = 1400.00
ROAD WIDENING AREA = 825.00
CENTRE LINE OF ROAD
EXISTING 30.00 MTS HIGHWAY
ROAD WIDENING AREA = 230.00
ROAD WIDENING AREA = 200.00
R/W LINE
78.00
13.00
9.00
53.00
29.00
8/1
TO VASCO
RAILWAY LINE
AIRPORT
NAVY GATE
TO VERNA
N
LOCATION PLAN
SCALE: NTS
FRONT COMPOUND WALL ELEVATION
FRONT COMPOUND WALL PLAN
SCALE 1:100
0.15 THK WALL
0.20X0.20THK BLOCK MASONRY PEIR
3.00
COMPOUND WALL PLAN
SCALE: 1:50
0.15 THK WALL
0.20X0.20THK BLOCK MASONRY PEIR
1.50
finished ground level
COMPOUND WALL ELEVATION
SCALE: 1:50
1.50
0.15 THK WALL
G.L
FOUNDATION TO DETAIL
0.40
SECTION THROUGH COMPOUND WALL
SCALE 1:50
SITE PLAN
SCALE 1:500
AREA STATEMENT IN SQ MTS
ZONE :- R1
1. AREA OF THE PLOT :- 7400.00 SMT.
2. AREA UNDER ROAD WIDENING :- 825.00 SMT.
3. EFFECTIVE AREA OF PLOT :- = 6575.00 SMT.
4. PERMISSIBLE F.A.R. 1.50 :- (=9863.00 SMT.
EFFECTIVE PLOT AREA X 1.00 + ROAD WIDENING AREA X 1.00)
= 6575.00 X 1.00 + 6575.00 SMT. + 825 X 1.00 = 825.00 SMT.)
SINCE R/W AREA IS LESS THAN 25% OF EPA
= 7400.00 SMT.
5. AREA OCCUPIED BY THE EXISTING BUILDING IN THE PLOT :- NIL
6. AREA OF THE BUILDING TO BE DEMOLISHED :- NIL
7. PERMISSIBLE COVERAGE = 40 % (2630.00 SMT.)
8. COVERED AREA OF PROPOSED BLOCKS :- RESIDENTIAL 1314.20 SMT.
COMMERCIAL 1316.20 SMT.
2630.39 SMT. = 39.99%
9. 15% OPEN SPACE PROVIDED = 1477.50 SMT. = 22.48%
10. DETAILS AREA AND USE, FLOOR WISE
RESIDENTIAL
FLOOR & REFERENCE | USE | TO TAL BUILT UP AREA SQM | AREAS FREE FROM FAR: BALCONY SQM | ELECTRICAL ROOM | STAIRCASE / LIFT | PARKING AREA | TOTAL DEDUCTIONS AREA SQM | NET FLOOR AREA FAR (SQM)
BASEMENT | CAR PARK | 1440.50 | - | - | 51.97 | 1215.75 | 1267.64 | 0.00
STILT | CAR PARK | 975.84 | - | - | 39.91 | 321.61 | 882.93 | 17.52
UPPER GROUND | RESIDENTIAL | 1062.12 | 217.95 | - | 107.78 | 71.44 | 397.09 | 1145.14
FIRST | RESIDENTIAL | 1062.12 | 229.02 | - | 107.78 | - | 334.80 | 1227.76
SECOND | RESIDENTIAL | 1062.12 | 226.02 | - | 107.78 | - | 334.80 | 1227.76
THIRD | RESIDENTIAL | 1062.12 | 226.02 | - | 107.78 | - | 334.80 | 1227.76
FOURTH | RESIDENTIAL | 1062.12 | 226.02 | - | 107.78 | - | 334.80 | 1227.76
TERRACE | STAIRCASE & LIFT MACHINE ROOM | 106.00 | - | - | 106.83 | - | 106.83 | -
COMMERCIAL
BASEMENT | CAR PARK | 1023.50 | - | - | - | 1263.02 | 1263.02 | -
GROUND | COMMERCIAL | 1062.12 | 5.88 | - | 6.68 | - | 12.56 | 1273.61
MID LEVEL | COMMERCIAL | 53.07 | - | - | 5.68 | - | 5.68 | 85.79
TOTAL | | 9863.39 | 1135.89 | - | 762.50 | 2171.81 | 5885.75 | 7760.75
11. ACHIEVED FAR :- 7760.75 SMT. / 7400.00 SMT.
12. PARKING DETAILS
FLOOR AREA SQM | USE | NO. OF CAR PARKS/PARKING AREA PROVIDED | REQUIRED
1323.62 SQM | RESIDENTIAL | 100 | 66
1323.62 SQM | COMMERCIAL | 38 | 26
13. TOTAL LENGTH OF BALCONIES
FLOOR | BUILDING PERIMETER (M) | BALCONY LENGTH (M) | BALCONY AREA (SMT)
UPPER GROUND | 226.00 | 144.72 | 217.00
FIRST | 241.00 | 149.72 | 224.50
SECOND | 241.00 | 149.72 | 224.50
THIRD | 226.00 | 149.72 | 224.50
FOURTH | 226.00 | 149.72 | 224.50
COMMERCIAL
GROUND FLOOR | 241.00 | 5.99 | 5.99
TOTAL | | 749.89 | 1121.49
APPROVED
DEVELOPMENT PERMISSION
Secretary
V. P. Chicalim
Mormugao- Goa
APPROVED
Panch. No. 3(20) Rem. 857/09/2011
Ref. No. VPC-II-57/Rem-13/2011/1018
Dated 13/09/2011
ARCHITECT'S SIGNATURE
K.R. MOHAN
ER/0049/2011
OWNER'S SIGNATURE
POA HOLDER FOR OWNER
M/S UMIYA BUILDERS & DEVELOPERS
PROJECT
PROPOSED COMMERCIAL CUM RESIDENTIAL BUILDING AT PLOT-C SY. NO. 8/1, FOR M/S UMIYA BUILDERS & DEVELOPERS OPP: AIRPORT AT VILLAGE SADOLIM OF MARMUGAO TALUKA, GOA.
TITLE
SITE PLAN, COMPOUND WALL & LOCATION PLAN
SCALE :- 1:200, 1:500 & 1:50
SHEET
AR-01
DATE 8-07-2011
ARCHITECTS
TEAM - 2
302,EMBASSY CHAMBERS
VITTAL MALLYA ROAD
BANGALORE 560 001